

Tank Removal

Client - Confidential



GES provided CEM services for 2-10,000 gallon tank removal projects. The CEM observed the tank removal, collected soil samples up to 2 feet below the tank bottoms and had them analysed for TPH EPA method 8015 Modified on a 24-hour turn around. The site activity log was prepared and submitted along with the analytical results to the client.